MYSORE DIVISION.

Dated 12th March 1917.

Notice is hereby given that sealed tenders will be received at the office of the President, City Municipal Council, Mysore, up to end of March 1917, for extending Devaraj Market Blocks A. and F. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1917.

2. The plans, detailed estimates and conditions may be seen at the Municipal Engineer's Office at Town Hall, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending Blocks A. and F. of Devaraj Market" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Municipal Council, Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Municipal Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

An approximate estimate of the quantities required for the work.

Details of work	Per	Quantity	Remarks
Earthwork excavating foundation and filling in basement	C. yd.	521	
Concrete filling in foundation	C. ft.	5,671	
Burnt brick in mortar foundation and basement	,,	8,300	
Do superstructure	,,	17,869	
Do plain archwork	,,	32	
Do foliated archwork	,,	50	
Cut stone in mortar, bases of pillars nicely dressed	No.	18	
Burnt stone slabs dressed 6" thick	Sq. ft.	2,503	
Teakwood panelled doors with hinges, locks and bolts, etc.	,,	2,319	
Do glazed ventilators rectangulars do	,,	368	
Do work wrought and put up, big scantlings	C. ft.	466·34	
Do do small scantlings	,,	1022·41	
Roofing with pukka terrace 9" thick, complete	Sq.	77·83	
Plastering with chunam	,,	292	
White and colour washing	,,	292	
Flooring with Cuddapah slabs over 3" concrete and cement pointing	,,	55	
Silicate painting	,,	53·74	
Dental cornice	R. ft.	64	
Cornice 9" thick ornamental	,,	555	
Do plain	,,	60	
Do 4½" thick for parapet	,,	592	
Ornamental parapet wall 2 ft. high	,,	180	
Do pediment over parapet wall	No.	2	
Do teakwood eave board 10" wide and 1" thick	R. ft.	180	
Do gate, complete	No.	2	
Masonry finials, large	,,	32	
Do small	,,	38	
Ornamental work for pedestals	,,	22	

T. G. LAKSHMANA RAO,
President.

KADUR DIVISION.

Dated 13th March 1917.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 15th April 1917, for constructing Police Lines at Sollebyle, Koppa Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A.M. and 5 P.M. on Office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (Two hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Lines at Sollebyle, Koppa Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

An approximate estimate of quantities for constructing Police Lines at Sollebyle, Koppa Taluk.

No.	Items of work.	Per	Quantity
1	Clearing site and levelling ground	Lump sum	Rupees
2	Earthwork excavation and filling basement	C. yd.	115
3	Concrete in mortar	C. ft.	1,032
4	Rough size stone in mud	"	2,331
5	Burnt brick in clay superstructure	"	2,146
6	Burnt brick in mortar	"	664
7	Reinforced concrete slabs	"	169
8	Plastering with mortar	Sq.	65'92
9	White and colour washing	"	65'92
10	Pointing basement with chunam	"	2'81
11	Honneywood work wrought and put up	C. ft.	80'20
12	Roofing with 1st class Mangalore tiles on teak reepers complete ...	Sq.	17'14
13	Ridge tiles set in mortar and pointed with cement	R. ft.	48
14	Flooring with 3" concrete and cement mortar plastered over	Sq.	9'17
15	Honneywood ornamental eave board with painting (9"×1")	R. ft.	263
16	Do battened door with frames, hinges and clamps, etc., complete ...	S. ft.	354
17	Do battened windows with frames, ½" iron bars and iron works, etc., complete...	"	35
18	Do ventilators with iron bars, shutters, etc., complete	"	15
19	Silicate painting to doors, etc.	Sq.	12'85
20	Binding walls over gables including plastering with mortar	R. ft.	61
21	Coping with brick in mortar and plastering complete	"	155
22	Providing smoke escape	No.	4
23	Constructing U-shaped drain in surki concrete and cement plastered	R. ft.	184
24	Wood oiling to wood work	Sq.	7'00
25	Gravel filling with consolidation	C. yd.	9
26	Providing wrought iron outlet pipe 1½" diameter	No.	8
27	Constructing seats and drains in latrine with brick in mortar and cement plastered ...	Lump sum	Rupees
28	Tarring wood work and floor of latrine and walls	"	
29	Finials and pendants	"	

K. PONNAPPA, *Executive Engineer.*

INDUSTRIES AND COMMERCE COMMITTEE.

Notification, Bedford House, Bangalore, dated 1917.

With a view to enable the local capitalists, expert cabinet-makers, or furniture firms, to tart an up-to-date Furniture Factory in the Bangalore City, with a minimum capital of Rs. 50,000, fifty thousand, the Industries and Commerce Committee are prepared to recommend the grant of all or any of the followiug concessions:—

1. A loan of 75 per cent of the value of the machinery, on delivery, at the Factory, carrying interest at 6¼ per cent per annum, repayable in annual instalments subject to a maximum period of 7 years.

The amount of the loan, however, shall not exceed 50 per cent of the value of machinery unless other security is furnished.

2. The machinery to be purchased should be approved by the Director of Industries and Commerce.

3. The loan will be subject to the conditions contained in the Rules relating to the grant of Takkavi loans for industries as regards repayment, inspection of the concern, and audit of accounts.

4. The loan, however, does not carry with it Government patronage.. The attention of the applicants is invited to existing rules relating to the supply of Departmental requirements, giving preference to indigenous manufactures, (*vide* Government Order No. Fl. 2760-809—G. F. 214-10-80, dated 23rd December 1913.

5. All timber available in the Forest Department, should be purchased by the Firm in public auction.

6. If the Forest Department is not able to offer seasoned wood, credit up to a maximum of Rs. 10,000, will be allowed to stand over, not exceeding 2 years, if the grantee furnishes proper security or makes other arrangements to the satisfaction of the Forest Department for punctual payment.

This concession will be in force only for 5 years.

7. Timber for which credit is given should be solely set apart for the manufacture of furniture.

Applications should be sent with full particulars to the undersigned on or before the 20th April 1917.

K. SUBBA RAO, *Secretary.*